Flo Design - Quotation (probe fixture)

Professional Services	-	Space planning and design consultation	1	Lot	0
Professional Services	-	3D perspective drawings for the living room and kitchen	2	Pieces	0
Professional Services	-	Project management and site coordination	1	Lot	0
Hacking	Living & Dining	Supply labour and tools to dismantle and remove existing lam	1	Lot	0
Hacking	Kitchen	Hack and remove existing floor and wall tiles, top and botto	1	Lot	0
Hacking	Common Bathroom	Dismantle existing sanitary wares and fittings; hack wall an	1	Lot	0
Hacking	Whole unit	Haulage and disposal of debris to an approved dumping site	1	Lot	3,200
Masonry	Kitchen	Apply cement plaster and skim coat to hacked kitchen wall	280	sqft	1,680
Masonry	Kitchen	Lay R10 slip-resistant homogeneous floor tiles with skirting	140	sqft	1,890
Masonry	Common Bathroom	Apply 3-coat waterproofing membrane with upturn	1	Lot	250
Masonry	Common Bathroom	Lay full-height homogeneous wall tiles	240	sqft	2,640
Masonry	Common Bathroom	Construct bathroom entrance kerb and shower drop	1	Lot	270
Carpentry	Kitchen	Design, fabricate and install kitchen top-hung cabinet with	18.5	ft run	2,405
Carpentry	Kitchen	Design, fabricate and install kitchen bottom cabinet with dr	12	ft run	1,680
Carpentry	Master Bedroom	Design, fabricate and install full-height casement wardrobe,	12.5	ft run	3,875
Carpentry	Living & Dining	Design, fabricate and install TV console with concealed LED	1	Lot	1,580
Countertop	Kitchen	Supply and install quartz countertop with 2 cut-outs	12	ft run	2,160
Plumbing	Kitchen	Install concealed copper piping for kitchen sink and washing	1	Lot	850
Plumbing	Common Bathroom	Install concealed copper piping for WC, bidet, basin tap and	1	Lot	1,600
Plumbing	Common Bathroom	Supply labour to install storage water heater, shower mixer,	1	Lot	0
Ceiling & Partition	Living & Dining	Construct L-box false ceiling with cove lighting	32	ft run	1,920
Electrical	Whole unit	Supply and install lighting points	18	point	1,260
Electrical	Whole unit	Supply and install 13A double power sockets	14	point	1,120
Electrical	Living & Dining	Supply and install KDK ceiling fan point with wiring	2	point	260
Glasswork	Common Bathroom	Supply & install tempered glass shower screen	1	set	780
Glasswork	Common Bathroom	Supply & install safety film for tempered glass shower scree	1	Lot	120
Painting	Whole unit	Paint internal walls of the entire unit, two coats emulsion	1	Lot	1,600
Cleaning	Whole unit	Chemical wash and general cleaning on handover	1	Lot	0